

SURVEY & REMONUMENTATION

APR 27 1995

LIBER

1 PG 1158

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo

(County)

Texas Township

Located in:

Corner Code #

1. Public Land Survey	T <u>3S</u> R <u>12W</u>	<u>G-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Thomas W. Chettleburgh
 CLERK - REGISTER

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 94 JUL 6 AM 11 52

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Thomas W. Chettleburgh, in a field survey on March 22, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 Corner Post set by U.S. Government Deputy Surveyor Thom Whelpley, 1829.
 Accessories: N62°W W.Oak 10" .62, S84°E W.Oak 14" .10
 F. Hodgeman, 1875, Set drill stone.
 E. Strong, 1913, Found stone and brick.
 Kalamazoo County Witness Sheet; Stone and Brick, 3/8" iron pin.
 A. McMachen, 1977, Found iron rod, recorded LCRC Liber 1, Page 756.
 D. Erickson, 1992, Found 1" bolt in centerline N-S road, recorded LCRC Liber 1, Page 975.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Original corner post and accessories not recovered.
 Found 1" bolt in centerline N-S road over drill stone 2.4' deep, checks corner location as described and recorded by A. McMachen & D. Erickson.
 The 1" bolt & drill stone was accepted as a careful and faithful perpetuation of the position of the original corner and was ratified by the Kalamazoo County Remonumentation Program Peer Group on April 21, 1994.
 Set 20" Harrison Monument and monument box directly over the found drill stone.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 4-21-94 *2.25*

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 20" Harrison Monument in monument box.
 SW side 2" dia. steel corner fence post N14°E 153.68'
 W side 2" dia. steel corner fence post N83°E 27.08'
 Spike N side 15" Sassafras N90°E 34.93'
 Spike N side 19" Hickory N86°W 45.37'
 Spike SW side 14" Walnut N49°W 48.33'



Signed by *Thomas W. Chettleburgh* Date July 5, 1994
 Surveyor's Michigan License No. 16036