

**SURVEY & REMONUMENTATION**

OCT 06 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Texas Township Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
Kalamazoo (County)

- 1. Public Land Survey T 3S R 12W G-8
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

LIBER 2 PAGE 172  
 COUNTY OF KALAMAZOO  
 RECEIVED FOR RECORD  
 STATE OF MICHIGAN  
 '97 JUL 29 PM 3 57  
 CLERK - REGISTER  
*Annally Brown*

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen in a field survey on June 11, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1829 - E. H. Lytle, D.S., Set quarter Section post, Wh. Oak 11" N. 41½° E. 23 lks., Wh. Oak 11" S. 06° E. 16 lks.
- 1870 - F. Hodgman, C.S., Found quarter Section corner from stumps of two witnesses. Planted stake and limestone from which Wh. Oak 14" N. 78° E. 54½ lks., Wh. Oak 12" S. 17° E. 75 lks.
- 1869 - F. Hodgman, C.S., "Stake, stone w/'X'."
- 1950 - Gove Assoc., "Stone w/'X'."

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found iron rod over stone with "X" with many smaller stones around. Stone with "X" is 18" deep, 0.7' West of N-S fence and 31.7' South of fence running to West only.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
 7-16-1997  
*R.E.S.*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Found stone is accepted as a careful and faithful perpetuation of the position of the original corner. Placed Harrison monument over found stone with monument box over, Accessories:

- "PK" Nail in S.W. side 10" Cherry S. 20° E. 15.25'
- "PK" Nail in North side 6" Cherry S. 80° W. 22.83'
- Nail & Tab in Easterly side 36" Oak S. 20° W. 23.8'
- Nail & Tab in Easterly side 12" Oak N. 40° W. 43.2'



Signed by *Allen H. McMachen*  
 Surveyor's Michigan License No. 16935

Date 7/25/97