

**SURVEY & REMONUMENTATION**

APR 27 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

DEC 30 PM 2 40

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
<u>Texas Township</u>	T <u>3S</u> R <u>12W</u>	<u>H-8</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*James J. [Signature]*  
CLERK-REGISTER

LIBER 1 PG 1246

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Thomas W. Chettleburgh, in a field survey on November 3, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 Corner Post not set by U.S. Government Land Surveys.  
 Ed Strong 1870, Set flat flint stone with cross at intersection of 1/4 lines.  
 Wilkins & Wheaton records, flat flint stone with cross  
 Accessories: fence intersection 2'S & 1'E  
 TW 12" Sassafras S40°W 6.5'  
 8" Mulberry S45°E 10.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found flat flint stone with cross from above witnesses.  
 The flat flint stone with cross was accepted as a careful and faithful perpetuation for the corner position as established and set by Ed Strong in 1870 and was ratified by the Kalamazoo County Remonumentation Program Peer Group on December 15, 1994.  
 Replaced flat flint stone (with cross) with 30" Harrison Monument.

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
12-15-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 30" Harrison Monument  
 Spike S side 18" Ash N85°E 38.99'  
 Spike E side 11" Sassafras Due South 25.75'  
 Spike NW side 18" Sassafras S35°W 6.00'  
 Spike NW side 15" Ash S50°W 20.72'  
 Spike NE side 13" Ash N35°W 7.97'



Signed by Thomas W. Chettleburgh Date December 22, 1994  
 Surveyor's Michigan License No. 16036