

AUG 22 1995

LAND CORNER RECORDATION CERTIFICATE, Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF KALAMAZOO RECEIVED FOR RECORD

95 APR 26 AM 11 09

For corners in COMMISSION

Table with columns: (County) Kalamazoo, Located In: Texas Township, Corner Code # I-1. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

James J. [Signature] CLERK-REGISTER

LIBER 1 1295

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. A star is marked at the intersection of column H and row 2.

I, Robert E. Snell, in a field survey on July 8, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1829: U.S. Government Survey; Enter North Boundary 150 Lks East of Post. Set Post at interseciton of Corners 2 and 3.
Burr Oak 18" South 22° West 265 Lks
Burr Oak 6" South 37° East 119 Lks
1874: Ed Strong, County Surveyor; Stone from U.S. Stump and New Witness jogs at N.E. Corner and North 1/4 are given wrong by U.S. Surveyor.
1881: Ed Strong, County Surveyor; Found stone.
B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1994: Found large stone below 5/8" x 4' iron rod. 5/8" x 4' iron rod placed over stone by county surveyor after locating stone by backhoe in 1960 survey. Original accessories gone.

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP 4-20-95 [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I-1 Northeast Corner Section 3, T. 3 S., R. 12 W.; Ratified by the Kalamazoo County Remonumentation Program Peer Group on April 20, 1995. Found large stone below original soil with a 5/8" x 4' iron rod over as called for in surveys done by Ed Strong, County Surveyor, in surveys dated 1874 and 1881 and is accepted as a careful and faithful perpetuation of the position of the original corner. Left stone in place and placed a 20" Harrison monument in monument box over stone after road reconstruction was completed.
PK Nail in Northwest Side (3' high) in Power Pole South 47° West 35.66'
PK Nail in Southwest Side (6' high) of 18" Oak North 35° West 50.02'
CL of Fire Hydrant North 76° West 73.72'
PK Nail in South Side (7' high) 22" Oak North 45° East 73.53'

Signed by [Signature] Date 4-26-95
Surveyor's Michigan License No. 9734