

FEB 08 1999

SECTION

LIDER

2 PAGE 386

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in TEXAS TWP KALAMAZOO (County)

Located In:

Corner Code #

Table with 3 columns: Description, T/R, Corner Code #. Includes rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Section.

- 4. Lot No. , Recorded Plat
5. Private Claims
6. IWM Job No. 24130

I, Allen H. McMachen, in a field survey on October 1, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1829 - E.H. Lytle, D.S., Set post, corner to Secs. 10, 11, 14 and 15, Wh. Oak 13" S. 85 1/2° E. 38 lks., Wh. Oak 18" N. 42° E. 110 lks..
1882 - F. Hodgman, C.S., "Set stake with stone around from stumps of 2 government bearing trees."
1911 - G. Wheaton, Set W 1/4 cor. on line & split.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod (no box) on the Northerly projection of a line between the S.W. corner (standard marker) and the W 1/4 corner (standard marker). Distance between SW corner and W 1/4 cor. was measured at 2635.25' and distance between W 1/4 corner and found iron at NW corner at 2635.10'. Corner appears to be in 10'-15' of fill.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1/2" iron is accepted as the best available evidence of the position of the original corner. Replaced found iron with a 30" Harrison Monument with monument box over, Accessories::

- "PK" Nail & Tab in North side of U. Pole S. 70° W. 22.94'
"PK" Nail & Tab in South side of U. Pole S. 70° E. 44.54'
Nail & Tab in SE side 10" Oak N. 35° E. 52.73'
Nail & Tab in South side 24" Oak N. 85° E. 87.30'

STATE OF MICHIGAN COUNTY OF KALAMAZOO RECEIVED FOR RECORD 98 DEC 15 PM 3 50 CLERK - REGISTER

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column I and row 5.

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP 11-19-1998



Signed by Allen H. McMachen

Date 12/15/98

Surveyor's Michigan License No. 16935