

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

DEC 30 PM 2 40

For corners in

Kalamazoo

(County)

Texas Township

1. Public Land Survey

Located In:

Corner Code #

T 3S R 12W

I-8

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Janet [Signature]

CLERK-REGISTER

LIBER

1 PG 1249

Register of Deeds Stamp & File Number

Thomas W.

I, Chettleburgh, in a field survey on November 3, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner Post set by U.S. Government Deputy Surveyor Thos Whelpley 1829

Accessories: 7" Red Oak N62 1/2° E 1.84 chains, 13" W. Oak N80 3/4° W 1.20 chains.

Ed Strong 1870, Found stake from one witness, set stone

Accessories: 12" Hickory N86 1/2° W 128 links, 4" Maple N89° E 62 1/2 links.

Ed Strong 1911, Found stone with cross

Accessories: 8" Hickory N80° W 43 1/2 links, 18" Maple N50° E 82 links.

Wilkins & Wheaton 1976 Found iron on West edge of pavement.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original corner post and accessories not recovered.

Found iron on West edge of pavement over stone with cross.

The stone with cross was accepted as a careful and faithful perpetuation of the position of the original corner and was ratified by the Kalamazoo County Remonumentation Program Peer Group on December 15, 1994.

Replaced stone (with cross) with 20" Harrison Monument & monument box.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12-15-94
R.E.F.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

20" Harrison Monument in monument box.

Spike in NW side 32" Maple N35° E 83.20'

Spike in S side 31" Maple S85° E 81.13'

Spike in S side 24" Hickory N80° W 29.07'

Spike in NE side 16" Walnut N20° W 61.20'

Centerline N-S Pav't 8th Street East 10.2'



Signed by

Thomas W. Chettleburgh

Date

December 22, 1994

Surveyor's Michigan License No.

16036