

SURVEY & REMONUMENTATION

1
2
OCT 06 1997

LIBER 2 PAGE 173

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Texas Township
Kalamazoo (County)

Located In:

Corner Code #

1. Public Land Survey	T	3S.	R	12W.	I-9
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

CLERK - REGISTER
Janet J. Brown

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
1997 JUL 29 PM 3 57

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____
- 6. IWM JOB #28120

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on June 19, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1829 - E. H. Lytle, D.S., Set post corner Section 22, 23, 26 & 27, Bl. Oak 11" S. 13° E. 35lks., W. Oak 9" N. 52½° W. 49 lks.
- 1870 - F. Hodgman, C.S., "Found stone set by former survey for Section corner, marked "+" stone and witnessed, Hickory 16" S. 80¾° E. 2.79 lks., Maple 6" N. 50° W. 95 lks.
- 1879 - F. Hodgman, C.S., "Stone of former survey."
- 1911 - Ed Strong, C.S., "Stone and brick" Apple 7" N. 33° E. 1.49'
- 1985 - Wilkins & Wheaton, "Stone", 14" Hickory N. 35° E. 58.03', P. Pole S. 25° E. 71.48', 18" Maple S. 65° W. 68.18', S.W. cor. house #8980 N. 45° E. 130.94', 1' N. and 1' E. of centerline - centerline.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Intersected 1985 witnesses and excavated through pavement finding pointed stone 6" below surface. Removed stone and found a second stone directly under first stone. Left second stone in place and placed Harrison Mon. at position of the point of first stone.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
7-16-1997**
R.E.F.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found stone is accepted as a careful and faithful perpetuation of the position of the original corner. Placed Harrison monument over found stone with monument box over, Accessories:

- "PK" Nail in S.W. side 10" Cherry S. 20° E. 15.25'
- "PK" Nail in North side 6" Cherry S. 80° W. 22.83'
- Nail & Tab in Easterly side 36" Oak S. 20° W. 23.8'
- Nail & Tab in Easterly side 12" Oak N. 40° W. 43.2'



Signed by *Allen H. McMachen*
Surveyor's Michigan License No. 16935

Date 7/25/97