

SURVEY & REMONUMENTATION

SEP 14 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 OR Liber Page 2 301

For corners in Texas Twp.

Kalamazoo
(County)

Located In:

Corner Code #

1. Public Land Survey

T 3S R 12W J-02

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

Filed for Record in
KALAMAZOO COUNTY, MI
TIMOTHY A SNOW
On 04-29-1998 At 09:05:34 a.m.
LAND CORNER 9.00
OR Liber 2 Page 301 - 301

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Robert E. Snell, in a field survey on April 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3				2				
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RES
RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP
4/16/98

A. Description of original monument and accessories and/or subsequent restoration:
This corner not set by original Government surveyors.

1940: Wilkins & Wheaton Engr. Co., County Surveyor; set iron on intersection of 1/4 lines
24" Maple S. 20° W. 26.6'
18" Maple N. 60° W. 14.8'

1977: Ingersol, Watson & McMachen (RLS #16935); L.C.R.C. Liber 1, Page 730, set iron by witnesses.
48" Oak W. 46.2'
48" Oak S. 15° E. 14.52'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
No Date: M.S.H.D., D. Bocks; 1" steel pin from witnesses.

1988: M.D.O.T. K. Schultz (RLS #31610); L.C.R.C. Liber 1, Page 891, steel pin.
NE cor. of SE Wingwall (Slope Dist.) N. 20° W. 53.22'
SE cor. of Conc. Drain Headwall N. 30° E. 26.72'
Nail/Tab in Guard Rail Post (Slope Dist.) N. 45° W. 31.11'
Nail/Tab in Guard Rail Post (Slope Dist.) S. 45° W. 33.50'
Center line 9th Street West 39.80;

1998: Reset iron by intersection of 1/4 lines, C 1/4 to N 1/4 2,924.14', C 1/4 to W 1/4 2,592.23', C 1/4 to S 1/4 2,649.66', C 1/4 to E 1/4 2,599.24'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-02: Center of Section 2, T. 3 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on April 16, 1998 and is accepted as a careful and faithful re-establishment of the established corner. This corner not established by original government surveyors. Placed 30" Harrison monument by intersection of 1/4 lines. After reconstruction of bridge on 9th Street over I-94.

Notch on corner of Concrete Wingwall N. 32°-07' W. 24.32'
NE corner of Inlet Casting S. 69°-59' W. 29.43'
NE corner of Inlet Casting S. 21°-20' W. 66.18'
Top of Curb at backside of East End of Off Ramp S. 28°-16' E. 98.56'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 4-28-98