

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in TEXAS TWP  
KALAMAZOO  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	3S.	R	12W.	J-5
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous Property in Section	S		T		
	S		T		

LIBER

2 PAGE 364

CLERK - REGISTER

*Handwritten signature*

98 OCT 22 PM 1 22

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

6. IWM Job No. 24130

I, Allen H. McMachen, in a field survey on September, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5										●			
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1829 - E.H. Lytle, D.S., Set quarter Section post, Bl. Oak 6" N. 14 1/4° E. 7 lks., Wh. Oak 14" S. 25 1/2° E. 24 lks..

1921 - A. Lenderink, Survey of Boy Scout property shows North quarter corner. **AS IRON**

1940 - A. Lenderink, Survey shows North quarter corner. **AS IRON**

1960 - W.D. Ingersoll, R.L.S., Reset corner per 1921 & 1940 Lenderink Surveys. S. 10° E. 36' to P.P. lines North and South tab West; N. 45° W. 52.51 feet to 30" Wh. Oak tab South side; N. 20° E. 36.92 feet to 15" R. Oak tab West side; East 47.20 feet to Northwest corner building foundation; S. 70° W. 12.86' to 12" Wh. Oak tab North side.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron rod per 1960 witnesses. Removed iron and dug to depth of 3 feet and found no additional evidence of corner.

SURVEY & REMONUMENTATION

NOV 25 1998

SECTION

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
10-16-1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Position of found iron rod is accepted as the best available evidence of the position of the original corner. Replaced found iron rod with a 20" Harrison Monument, Accessories:

- NW corner concrete foundation (Health Bldg.) S. 84° E. 47.18'
- Nail in North side of 18" Oak N. 76° E. 35.80'
- Nail in SE side of 18" Oak S. 89° W. 12.3'
- Nail in West side of P. Pole S. 05° E. 35.90'
- Iron rod S. 45° W. 3'
- Iron rod S. 45° E. 3'



Signed by

*Allen H. McMachen*  
16935

Date

10/21/98

Surveyor's Michigan License No.