

FEB 08 1999

LIBER 2 PAGE 390

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in TEXAS TWP KALAMAZOO (County)

Located In:

Corner Code #

- 1. Public Land Survey T 3S. R 12W. J-6
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

STATE OF MICHIGAN COUNTY OF KALAMAZOO RECEIVED FOR RECORD 98 DEC 15 PM 3 50 CLERK - REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims
6. IWM Job No. 24130

Grid table with columns A-L and rows 2-13. Cell J-14 is circled.

I, Allen H. McMachen, in a field survey on September, 19 98 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not placed by original government surveyors. 1953 - Wilkins & Wheaton, Measured from Center quarter corner to West quarter corner at 2623.79 feet. 1960 - W.D. Ingersoll, R.L.S., "Found pipe - Nothing beneath", North 35.54' 14" Red Oak,, East 61.10' 30" Wh. Oak, South 32.65' 18" Red Oak.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" I.D. pipe per 1960 information. Pipe is on line between W1/4 corner (standard marker) and E1/4 corner (standard marker). Pipe is +/- 2' West of a line between N1/4 corner (standard marker) and S1/4 corner (standard marker). Distance between Center quarter corner (pipe) and W1/4 corner (standard marker) was measured at 2623.91'.

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP 10-15-1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

This corner not established by original government surveyors. Found pipe is accepted as the best available evidence of the position of the corner. Replaced pipe with a 30" Harrison Monument, Accessories:

- Nail & Tab in West side 10" Twin Oak N. 30° E. 12.42'
Nail & Tab in South side 10" Twin Cherry East 10.01'
Nail & Tab in S.W. side 14" Oak S. 52° E. 25.87'
Nail & Tab in West side 10" Cherry S. 05° E. 23.80'
In stockade fence North and South



Signed by Allen H. McMachen 16935

Date 12/15/98

Surveyor's Michigan License No.