

OCT 06 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

'97 AUG 21 PM 3 49

For corners in Texas Township  
Kalamazoo  
(County)

Located In:

Corner Code #

*Smith*  
CLERK - REGISTER

LIBER 2 PAGE 187

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 3S. R 12W. J-7
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_
- 6. IWM Job No. 28120

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen in a field survey on June 19, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1829 - E.H. Lytle, D.S., Set quarter Section post, Bl. Oak 9" S. 57° E. 89 lks., W. Oak 30" S. 09° W. 71 lks..  
1992 - Original iron removed by sewer construction. Wilkins & Wheaton replaced with 1" iron in mon box at previous position.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" iron rod in mon. box. Any additional corner accessories would have been removed during sewer construction.

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
7-16-1997  
*R. E. V.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1" iron in monument box is accepted as the best available evidence of the position of the corner. Replaced iron rod with a Harrison monument and monument box, Accessories:

- Nail & Tab in Easterly side 36" Oak N. 05° E. 25.24'
- Nail & Tab in Southeasterly side U. Pole N. 50° E. 31.95'
- Nail & Tab in 18" Triple Oak S. 50° W. 39.36'
- Nail & Tab in Northerly side 30" Oak S. 55° W. 88.78'



Signed by Allen H. McMachen Date 8/20/97

Surveyor's Michigan License No. 16935