

OCT 06 1997

COMMISSION

1  
2

LIBER 2 PAGE 174  
'97 JUL 29 PM 3 57  
STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
CLERK - REGISTER  
*Annelle Johnson*

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Texas Township  
Kalamazoo (County) Located In: Corner Code #

- 1. Public Land Survey T 3S. R 12W. J-9
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Section S T R

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_
- 6. IWM JOB NO. 28120

I, Allen H. McMachen in a field survey on June 17, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1829 - E. H. Lytle, D.S., Set quarter Section post, Bl. Oak 18" N. 81 1/4° W. 64 lks., Bl. Oak 18" S. 37 1/2° E. 51 lks.  
1879 - F. Hodgman, C.S., "Found stake hole and part of stake from roots of one witness tree, set stone, brick and plow point and marked." Y. Oak 10" N. 75° E. 153 1/2 lks., DO. 20" N. 72° W. 110 1/2 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" iron rod, 18" long. Removed iron and found stone with dimple directly under iron. Stone had two plow points next to it, one on East and one on West.

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
7-16-1997  
*R. E. S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found stone is accepted as a careful and faithful perpetuation of the position of the original corner. Placed Harrison monument over found stone with monument box over, Accessories:

- Southwest corner house N. 10° E. 125.75'
- Northwest corner house S. 30° E. 46.63'
- Nail & Tab in South side 30" Oak N. 80° W. 136.43'
- Nail & Tab in Northerly side 12" Maple N. 45° E. 73.52'



Signed by *Allen H. McMachen*  
Surveyor's Michigan License No. 16935

Date 7/25/97