

AUG 22 1995

LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
STATE COUNTY OF KALAMAZOO
COUNTY RECEIVED FOR RECORD
RECEIVED 1995 APR 26 AM 11 09
RECORDS
CLERK-REGISTER

For corners in
Kalamazoo

Located In: Corner Code #

(County)
Texas Township

1. Public Land Survey	T 3 S R 12 W	K-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Jennifer Jones
CLERK-REGISTER

LIBER 1 1296

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert E. Snell, in a field survey on January 12, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1829: U.S. Government Survey; Enter North boundary 96 Lks East of Post. Set Post at intersection of Corner Sections 1 and 2.

Wh. Oak 9" South 50° West 149 Lks
Wh. Oak 9" South 82° East 511 Lks

1911: Ed Strong, County Surveyor; Northeast Corner stone W. Oak South 45° West 28 Lks

1992: Wilkins & Wheaton Engineering Company; Found "T" iron fitting old witness for Northeast Corner Section 2, Texas and 63.38 East of iron set for Southeast Corner Section 35, Oshtemo. (Government Jog=63.36').

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993: Replaced Northeast Corner Section 2 from witnesses following sewer and road reconstruction. Original corner lost in sewer construction.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12-16-93

R.E.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 Northeast Corner Section 2, T. 3 S., R. 12 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on December 16, 1993. Found iron in monument box as replaced following sewer construction and is accepted as careful and faithful perpetuation of the position of the original corner. Placed 20" Harrison monument in monument box.

Monument in Monument Box (K-13; T. 2 S., R. 12 W.)	West	63.37'
(MSHD) Nail/Tab in North Side	South 71° East	78.14'
Northeast Corner	South 20° East	56.90'
(MSHD) Nail/Tab in North Side	South 73° West	60.74'
(MSHD) BM Tab in Southwest Side	North 63° West	61.61'

Signed by *Robert E. Snell*

Date 4-26-95

Surveyor's Michigan License No. 9734