

FEB 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 394

For corners in Texas Twp.

Kalamazoo
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|----------------|-------|
| 1. Public Land Survey | T3S R12W | K-02 |
| | T___ R___ | _____ |
| | T___ R___ | _____ |
| | T___ R___ | _____ |
| 2. Property Controlling in Section | S___ T___ R___ | _____ |
| | S___ T___ R___ | _____ |
| 3. Miscellaneous Property in Sec. | S___ T___ R___ | _____ |
| | S___ T___ R___ | _____ |

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 DEC 23 AM 9 15
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on March 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

- A. Description of original monument and accessories and/or subsequent restoration:
1829: United States Government Surveyors; set 1/4 Section post.
W. Oak 6" S. 69 3/4° E. 40 lks.
W. Oak 6" S. 86 1/4° W. 58 lks.
1879: E. Strong, County Surveyor; W 1/4 post, Section 1, No description of monument shown and no witnesses. Shows distance from NW 1/4 Section 1 to W 1/4 Section 1 as 44.78 ch = 2,955.48'

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
4/16/98

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1938: State of Michigan (MSHD); found stone, brought up with iron, in fence corner N., S., & W. 18" Oak S. 02° W. 46.0' 8" Oak North 63.9' 6" Sassafras West 45.20' 18" Oak S. 02° W. 46.75'
1940: Wilkins & Wheaton Engr. Co.; found stone & iron.
1957: MSHD; 1/2" iron 12" Oak N. 01° E. 63.38' 22" Oak South 46.65' 6" Sassafras S. 81° W. 45.19'
1968: Wilkins & Wheaton Engr. Co.; set monument.
1998: Found 3" square x 36" plat monument with large stones around. One stone appeared to have drill mark.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-02: East 1/4 Post, Section 2, T. 3 S., R. 12 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on April 16, 1998 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" sq. x 36" monument with stone beside. Monument set in place of stone & iron in 1968 by Wilkins & Wheaton Engr. Co., County Surveyor. Replaced monument with 30" Harrison monument.
PK Nail over exist. Nail in North Side 22" Oak S. 86° E. 17.47'
Nail/Tab (MSHD) in North Side 14" Oak S. 24° E. 24.07'
Northeast Corner Modular Home S. 40° W. 18.48'
PK Nail in North Side 24" Oak N. 88° W. 30.92'
South R-0-W Fence I-94 North 23.25'

Signed by Robert E. Snell Date 12/18-98
Surveyor's Michigan License No. 9734