

NOV 25 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Texas Twp.

Kalamazoo  
(County)

Located In: Corner Code #

- |                                    |                          |             |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey              | T <u>3S</u> R <u>12W</u> | <u>L-05</u> |
|                                    | T _____ R _____          | _____       |
|                                    | T _____ R _____          | _____       |
|                                    | T _____ R _____          | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____       |
|                                    | S _____ T _____ R _____  | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____       |
|                                    | S _____ T _____ R _____  | _____       |

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
98 OCT 22 PM 11 37  
CLERK - REGISTER  
1888 2PAGE 354  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on Aug. 8, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**

A. Description of original monument and accessories and/or subsequent restoration:

1829: United States Government Surveyors; set 1/4 Section post.

W. Oak 9"                      N. 70 $\frac{1}{2}$ <sup>0</sup> E.                      202 lks.  
Hickory 6"                      S. 29 $\frac{1}{2}$ <sup>0</sup> W.                      112 lks.

1882: E. Strong, County Surveyor; bisected South line, placed stone at South 1/4 post.

Hickory 4"                      S. 3<sup>0</sup> W.                      51 lks.

1910: E. Strong, County Surveyor; measured South 1/4 to Southeast corner, 39.46 $\frac{1}{4}$  chains = 2,604.525.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1941: Wilkins & Wheaton Engr. Co.; found stone and crockery, placed iron.

6" Hickory                      West                      22.25'  
East & West Fence South                      2.0'  
North & South Fence West                      5.0'  
14" Oak                      North                      72.8'

1963: Wilkins & Wheaton Engr. Co.; found iron from Section notes, 2' North of East & West fence (West) and about 5' East of North & South fence, 72.8' Southerly of 26" Oak.

1998: Found  $\frac{1}{2}$ " x 18" iron (rebar) at surface. Found  $\frac{1}{2}$ " x 12" iron laying on its side along 2 cobble size stone with crockery and glass around.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-05: South 1/4 post, Section 12, T. 3 S., R. 12 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on August 8, 1998 and is accepted as the best available evidence of the position of the original corner. Found  $\frac{1}{2}$ " x 18" rered set after 1941 from witnesses. Placed 30" Harrison monument in place of iron.

PK Nail in East Side                      24" Oak                      N. 12<sup>0</sup> W.                      27.30'  
PK Nail in North Side                      18" Hickory                      West                      22.51'  
PK Nail in South Side                      24" Oak                      S. 82<sup>0</sup> E.                      56.27'  
Exist. Nail/Tab in North Face                      RR Rail Fence Post                      S. 72<sup>0</sup> W.                      4.88'

Signed by Robert E. Snell  
Surveyor's Michigan License No. 9734

Date 10-22-98