

APR 01 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

96 JAN 23 PM 3 50

For corners in  
Kalamazoo  
(County)  
Texas Twp.

Located In:

Corner Code #

- 1. Public Land Survey      T 3 S. R 12 W.      M-04
- T    R
- T    R
- T    R
- 2. Property Controlling    S    T    R
- in Section                S    T    R
- 3. Miscellaneous            S    T    R
- Property in Section      S    T    R

*James Young*  
CLERK-REGISTER

LIBER **1 1437**

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on June 8, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: United States Government Surveyors; set 1/4 Section post.  
      Y. Oak 17"      S. 12° W.      63 lks.  
      W. Oak 16"      N. 08° W.      53 lks.
- 1910: E. Strong, County Surveyor; stakes, stone, brick.  
      Y. Oak 20"      S. 88° W.      56 lks.

1910: E. Strong, County Surveyor; found brick, set stone for Portage corner North 35 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found 1" pinch pipe 20" long in monument box, pieces of brick were scattered around the pipe. Dug to a depth of 3' and found no other evidence. Measurement from corner to West 1/4 post Section 7 was 23.14'. Previous measurement was 23.10' (35 lks.). Measurement from East 1/4 post Section 12, Texas (M-04) to Northeast corner Section 12, Texas (M-03) is 2,659.17'.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
7-20-95**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-04: East 1/4 post Section 12, T. 3 S., R. 12 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on July 20, 1995 and is accepted as best available evidence of the position of the original corner. Found 1" pinch pipe, 20" long in monument box with brick pieces around it. Placed a 20" Harrison Monument in monument box after road reconstruction.  
Harrison Monument (East 1/4 post Section 7, T. 3 S., R. 11 W.) North 23.14'

- PK Nail in W./side      20" Walnut      N. 62° E.      38.89'
- PK Nail in S./side      38" Oak          S. 88° W.      36.73' (Strong Witness)
- PK Nail in S./side      Power Pole      N. 30° W.      71.66'
- Center Line            Sanitary Manhole South      28.06'

Signed by Robert E. Snell

Date 1-18-96

Surveyor's Michigan License No. 9734