

NOV 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'95 AUG 25 PM 3 51

For corners in
Kalamazoo
(County)

Located In:

Corner Code #

Texas Township

- 1. Public Land Survey T 3 S R 12 W M-6
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

Handwritten signature of Clerk-Register

CLERK-REGISTER

LIBER 1 1326

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. Cell 6,13 contains a circled 'X'.

I, Garth N. Baden, in a field survey on August 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1825: United States Government Surveyors; Set 1/4 Section Post.

W. Oak 6" South 45° West 31 Lks
W. Oak 6" North 67° West 21 Lks

1959: Wilkins & Wheaton Engineering Company; Placed iron 24.75' South of West 1/4 Post, Section 18, T. 3 S., R. 11 W. (Portage A-6).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found 5/8" x 24" Iron in monument box. Found evidence of digging to a depth of 4' below pavement.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

6-15-95

Handwritten signature of Peer Group member

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 East 1/4 Post Section 13, T. 3 S., R. 12 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on June 15, 1995 and is accepted as a careful and faithful re-establishment of the position of the original corner. Found 5/8" x 24" iron in monument box. Replaced with a 20" Harrison monument and monument box after sewer construction.

Exist. Nail/Tab in North Side 36" Oak South 60° East 23.92'
Exist. Nail/Tab in South Side Power Pole North 80° East 63.78'
Exist. Nail/Tab (Upper Tab) in North Side Power Pole West 37.44'
PK Nail in Northeast Side 26" Oak North 22° West 67.14'

Signed by [Handwritten Signature]

Date Aug 22, 1995

Surveyor's Michigan License No. 10679