



LC-000045
Page: 1 of 1
10/28/1999 03:11P
Bk-2 Pg-498

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

FEB 08 2000

SECTION

Register of Deeds Stamp & File Number

For corners in

<u>Kalamazoo</u>	Located In:	Corner Code#
(County)		
Wakeshma Twp.		
1. Public Land Survey	T <u>4S</u> R <u>9W</u>	<u>A4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, Gary D. Hahn, in a field survey on August 5, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner not established by the G.L.O. Survey.
1876 - F. Hodgman: "Located E 1/4 post sec. 12 from stump of Ash bearing tree. Marks plain. Then ??? South 160 lks. and set stake w/stone and earthen around".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered. Found a 1/4" diameter 9" long rod in a 2 1/2" diameter 3" long pipe in the asphalt road. Rod is 105.49 feet South of the surface marker (1/2" rebar) at Brady corner M4. Removed rod. Found a 1" diameter 4.5' long pipe 2' below the road surface. Pipe was 0.67 feet North of the surface rod. Removed pipe. Found an 8" x 10" x 13" stone with a point but lying flat side up. Center of stone was 1.63 feet South and 2.43 feet East of the 1" pipe. Set the stone point up in place of the 1" pipe at a depth of 22" below the road surface. Believe stone was disturbed. Found no evidence of earthen around stone. The Kalamazoo County Remonumentation Peer Group determined that the best location to reestablish this corner is on line between Brady Township corners M4 and M5 at a distance of 105.60 feet South of said corner M4."

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A4, West Quarter Post of Section 7, Town 4 South, Range 9 West. Ratified by the Kalamazoo County Remonumentation Peer Group on September 23, 1999. The above described corner position is accepted as a careful and faithful reestablishment of the position of the original corner. Set a 20" Harrison Monument in a monument box at said position.

Witness Ties: Found PK nail in 20" Hickory N 74 ° E 35.79'
Found PK nail in Fence Post East 34.21'
Set 1/2" rebar S 45 ° W 20.91'
Set PK nail in 10" Ash N 28 ° W 61.33'

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-23-1999



Signed by [Signature]
Surveyor's Michigan License No. 38116

Date 10/18/99

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS,
JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983 REVISED OCT., 1995