

FEB 08 1999

LIBER 2 PAGE 405

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 DEC 23 AM 3 05
Clerk - Register
Annaly Johnson

For corners in

Kalamazoo (County)	Located In:	Corner Code#
Wakeshma Twp.		
1. Public Land Survey	T 4S R 9W	A7
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Gary D. Hahn, in a field survey on October 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826 - Established by U.S. Deputy Surveyor Robert Clark, Jr.
Sycamore 24" N 29 E 15 Lks.
Elm 20" S 49 E 25 Lks.

1873 - F. Hodgman - "Found stake from stump of one witness. Set new stake and marked."
Beech 8" N 26 1/2 E 119

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998 - Found 1/2" iron in mon. box. Removed. Fnd. 1/2" rebar, 1 1/2' below road surface 0.07' south and 0.05' west of 1/2" iron. Removed. Fnd. 2" dia. well point 2.7' below surface. Removed. Dug a 4'x6'x6' deep hole into clay layer. No evidence of "stake" found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7, Southwest Corner Section 18, Town 4 South, Range 9 West, ratified by Kalamazoo County Remonumentation Peer Group on November 19, 1998. Position of the well point is accepted as the best available evidence of the position of the original corner. Set 30" Harrison Monument in a Monument Box in place of well point.

Witness Ties:

- Fnd. Harrison Monument in mon. box North 74.29'
- Set Mag. Nail in 4" Poplar S 38'E 52.85'
- Set Mag. Nail in 8" Oak S 28'W 62.56'
- Set Mag. Nail in Guard Post N 31'W 74.12'

Signed by *Gary D. Hahn*
Surveyor's Michigan License No. 38116

Date 12/08/98
FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS,
JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983 REVISED OCT., 1995

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

11/19/98 F.

