

APR 01 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

95 DEC 8 AM 10 55

For corners in
Kalamazoo
(County)

Located In:

Corner Code #

Wakeshma Twp.

1. Public Land Survey	T <u>4S</u>	R <u>9W</u>	<u>B5</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Section	S _____	T _____	R _____
	S _____	T _____	R _____

James Young
CLERK-REGISTER

LIBER 1 1406

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5	●											
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Gary D. Hahn, in a field survey on May 1, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1826 Quarter corner established by U.S. Deputy Surveyor Robert Clark, Jr.
Accessories: Beech 10in N47½W 37 lks. Beech 7in S35W 30 lks.
- 1884 Hodgman "Rock found by R. Nutting surveyor"
- 1885 F. Hodgman Co. Sur. "Cornerstone by R. Nutting w/side stones 50 lks. North and South."

Date? KCRC (plan/profile sheet "V" Ave.) Stone Poplar 12" S75 W 75.5'
Elm 26" N70°W 93.4' Walnut 14" N2°W 82.9'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered.

Found 20" x 20" x ? flat rock with 3/4" drill hole on north side of top. This rock was found 16" below top of asphalt road.

Believe to have found "side stone" to south 32.98'

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP**
6-15-95 *R.D.H.*



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B5, South Quarter corner Section 7, T4S, R9W, Wakeshma Township, Ratified by Kalamazoo County Remonumentation Peer Group on June 15, 1995. The position of the drill hole on the rock is accepted as a careful and faithful perpetuation of the position of the original corner. Set a modified (11") Harrison monument over drill hole in a monument box.
Found 12"x18" stone South 32.98'
Set P.K. nail in 35" Black Walnut N2°W 82.80'
Fnd. P.K. nail in P.P. N20°E 32.74'
Fnd. nail with tab in P.P. N2°W 31.94'
Fnd. nail with tab in 20" Black Walnut S72°W 90.68'

Signed by *Gary D. Hahn*

Date December 5, 1995

Surveyor's Michigan License No. 38116