

FEB 08 1999 LIBER

2 PAGE 406

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF KALAMAZOO RECEIVED FOR RECORD 98 DEC 23 AM 3 05

For corners in

Form with fields for Kalamazoo (County), Located In: Wakeshma Twp., Corner Code#: C7, and sections for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

Register of Deeds Stamp & File Number

I, Gary D. Hahn, in a field survey on October 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826 - Established by U.S. Deputy Surveyor Robert Clark, Jr. Beech 6" N 68 E 17 1/2 Lks. Beech 8" S 77 W 21Lks.

1866 - F. Stinson - "Found corner by former survey tree gone. Planted sotne 18 x 24 inches 3 inches out of ground."

1873 - F. Hodgman - "Stone of some former survey. See p. 54"

KCRC Witness Ties: 20" Walnut S 30 E 52.82' SW - Cor Hse. Bottom stone 73.04'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998 - Original monument and accessories not recovered. No surface marker found. Found 12" x 15" round stone with flat top with high point. Also found 2" x 2" wood stake lying west of and next to stone. Excavated a 6' x 8' hole 5' deep. Probed around stone - found no other stone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7, Southeast Corner Section 18, Town 4 South, Range 9 West, ratified by Kalamazoo County Remonumentation Peer Group on November 19, 1998. Position of the stone is accepted as a carefull and faithful perpetuation of the position of the original corner. Set 30" Harrison Monument in a Monument Box directly over stone.

Witness Ties: Set Mag. Nail in 30" Walnut S 30'E 54.21' NE. Corner of house foundation S 45'W 73.86' Set 1/2" rebar N 51'E 49.90' Set 1/2" rebar N 38'W 37.68'

Signed by Gary D. Hahn Surveyor's Michigan License No. 38116

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP 11/19/98

Grid table with columns A-L and rows 1-13. A dot is marked at row 7, column C.



Date 12/08/98 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS. JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983 REVISED OCT., 1995