

SURVEY & REMONUMENTATION

FEB 26 1998

LIBER 2 PAGE 234

7
2
SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Wakeshma Township

Kalamazoo (County)	Located In:	Corner Code #
1. Public Land Survey	T4S R 9W	E-02
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
97 NOV 26 PM 1 32
Clerk - Register

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on July 22, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
8/2/1997

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5	4			3		2		1	
3													
4	7			8	9			10		11		12	
5													
6	18			17	16			15		14		13	
7													
8	19			20	21			22		23		24	
9													
10	30			29	28			27		26		25	
11													
12	31			32	33			34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1826: United States Government Surveyors; set 1/4 section post.
Beech 6" S. 82 1/2° W. 19 1/2 lks.
Beech 7" S. 30° E. 14 lks.
- 1871: F. Hodgman, County Surveyor; "8 (West 1/4 post, Section 4) found 1/2 Section corner stake from one witness stump. Drove new stake and marked (Nutting witnesses)
Beech 12" N. 23° W. 84 lks.
Beech 12" S. 03° E. 65 lks.
- 1885: F. Hodgman, County Surveyor; "6 (East 1/4 post, Section 5) found old stake and set stone with brick around, South side of wagon track."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1976: Wilkins & Wheaton Engineering Co., Inc., R. E. Snell #9734; L.C.R.C. L-1, P-672, found stone and brick.
P.P. N. 10° E. 27.0'
Tel. Pole S. 05° E. 23.0'
S.W. Corner House #12955 N. 05° E. 82.3'
- 1997: Found (8"x8"x12") stone with brick around just below surface of gravel road, R.R. rail fence corner North 33.3'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-02: West 1/4 post, Section 4, T. 4 S., R 9 W., ratified by the KCRPPG on August 21, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found stone set by F. Hodgman, County Surveyor in an 1885 survey. Lowered stone and placed a 20" Harrison monument and monument box over stone.
P.K. nail in West side Power Pole N. 32° E. 26.77'
P.K. nail in North side Triple 12" Ash S. 10° E. 23.14'
P.K. nail in East side 12" Maple N. 06° E. 40.48'
Southwest corner house foundation (12955 "TU" Ave.) N. 14° E. 82.30'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date Nov. 3, 1997