

FEB 08 1999

LIBER

2 PAGE 407

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo	Located In:	Corner Code#
(County)		
Wakeshma Twp.		
1. Public Land Survey	T 4S R 9W	E7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
98 DEC 23 AM 3 05  
*Amelia Steward*  
CLERK - REGISTER

Register of Deeds Stamp & File Number

I, Gary D. Hahn, in a field survey on October 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826 - Established by U.S. Deputy Surveyor Robert Clark, Jr.  
Beech 15" N 82 E 18 1/2 Lks. Beech 8" N 87 W 10 1/2 Lks.

1866 - F. Stimson - "Stone planted by Nutting (surveyor) + hole drilled in top of stone. Trees gone. Stones & rods E & W referenced."  
1872 - S. Hodgman - "Rocks bounds" by R. Nutting - surveyor.

KCRC Witness Ties:  
T.P. S 45'E 70.65'  
23" Maple S 45'W 66.87'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998 - Original monument and accessories not recovered. Found large stone with drill hole 3.5' ± below surface. Stone had a 1/4" dia. rod sticking out of drill hole. Rod was surrounded by four 8" - 12" dia. round stones.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7, Southeast Corner Section 17, Town 4 South, Range 9 West, ratified by Kalamazoo County Remonumentation Peer Group on November 19, 1998. Position of the drill hole in stone is accepted as a carefull and faithful perpetuation of the position of the original corner. Set 30" Harrison Monument in a Monument Box directly over drill hole.

Witness Ties:

Set Mag. Nail in 27" Maple S 20'W 66.57'  
Set Mag. Nail in P.P. S 38'W 64.57'  
Set 1/2" rebar S 42'E 56.70'  
Center of top of telephone riser box N 52'E 53.12'

Signed by *Gary D. Hahn*  
Surveyor's Michigan License No. 38116

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
11/19/98 *R. C. O.*

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												



Date 12/08/98  
FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS,  
JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983 REVISED OCT., 1995