

SURVEY & REMONUMENTATION

FEB 26 1998

SECTION

LIBER 2 PAGE 235

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Wakeshma Township

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
97 NOV 26 PM 1 32
Clerk - Register
[Signature]

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4S</u> R <u>9W</u>	<u>E-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert F. Snell, in a field survey on July 25, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, shall be recorded on this certificate.

APPROVED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
8/21/97 R. 98

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1826: United States Government Surveyors; set post, corner to sections 28, 29, 32 & 33. Sugar 8" N. 61 1/2° W. 22 lks. Cherry 18" N. 78° E. 17 lks.
 - 1872: S. Hodgman, Deputy County Surveyor; "Rockbounds" by Nutting, Surveyor. Witness stumps good."
 - 1874: F. Hodgman, County Surveyor; "(1) (Northeast corner, Section 33) found corner stone of former survey."

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1968: Wilkins & Wheaton Engineering Co.; Found drilled stone.
Large flat (stone) Westerly notch cut at 29.0'
Railroad rail fence post Southeast 41.82', 12" Gypole N. 60° E., 75.29'
12" Black Walnut S. 75° E., 103.8'
 - 1974: D.M. Drener, RLS #13580; L.C.R.C. L-1, P-385, large stone with hole in top.
Centerline 30" Willow N. 85° W. 34.0'
"T" Rail S. 45° E. 42.0' (in line with stone wall West)
Centerline telephone pole N. 60° E. 76.0'
 - 1997: Found stone with drill mark down about 24" with small stones around.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.
- E-11: Southwest corner, Section 28, T. 4 S., R. 9 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on August 21, 1997, and is accepted as a careful and faithful perpetuation of the position of the original corner. Found stone with drill mark as set in a survey previous to 1872 by R. Nutting, Surveyor. Placed 20" Harrison Monument over stone and a monument box over monument, 3" below surface of gravel road.
P.K. nail in South side 10" Elm S. 86° W. 27.74'
P.K. nail in West side 12" Walnut S. 12° E. 72.63'
P.K. nail in West side 12" Ash N. 30° E. 86.07'
Southeast Edge Railroad Rail Fence Corner S. 25° E. 42.32'

Signed by *Robert F. Snell* Date Nov. 3, 1997
Surveyor's Michigan License No. 9734