

SURVEY & REMONUMENTATION

FEB 08 2000

Sequence #1

LIBER 2 PAGE 451

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo (County)	Located In:	Corner Code#
Wakeshma Twp. 1. Public Land Survey	T 4S R 9W	F-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 99 FEB 11 PM 1 08
Janice J. Brown
 CLERK - REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Gary D. Hahn, in a field survey on October 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1826 - Quarter post established by U.S. Deputy Surveyor Robert Clark, Jr.
Beech 13" S 78°W 12 lks. Beech 5" N 26½°E 10 lks.
- 1872 - Samuel Hodgman - "Stone with drill hole and side stones N & S 50 lks.

KCRC Witness Ties:

- (W) Maple 24" N 2°W 29.05'
- (W) Maple 16" N 35°W 33.55'
- (W) Maple 20" S 15°E 26.65'
- (W) Stone set 33' N & S
- (W) Drilled stone by (H)
- NE cor. house 52.25'
- NW cor. house 70.06'

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 12-17-1998
R.E.S.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered.
 1998: No surface marker found. Excavated a 7' (N & S) x 17' (E & W) x 7' deep hole centered on bisection of line between SE & SW corners. Found no evidence of stone with drill hole. Area may have been excavated for road. Side stone to north gone due to fiber optic installation. Side stone to south gone due to driveway cut. Reestablished corner at bisection between the previously ratified southwest and southeast corners of section 16.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7, South Quarter Post, Section 16, Town 4 South, Range 9 West. Ratified by the Kalamazoo County Remonumentation Peer Group on December 17, 1998. Set a 20" Harrison Monument in a monument box at the above described bisection. This position is accepted as a careful and faithful reestablishment of the position of the original corner.

Witness Ties:

- SW cor. house foundation N 40°W 69.41'
- Found 4" x 8" oblong stone flat side up north 31.97'
- Set Mag. Nail in 11" Hickory N 15°E 45.91'
- Set Mag. Nail in P.P. S 49°E 41.94'
- Set Mag. Nail in 18" Pine S 62°W 65.29'



Signed by *Gary D. Hahn*
 Surveyor's Michigan License No. 38116

Date 02/09/99
 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS,
 JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983 REVISED OCT., 1995