

SURVEY & REMONUMENTATION

FEB 26 1998

LIBER 2 PAGE 236

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Wakeshma Township

Kalamazoo
(County)

Located in:

Corner Code #

- | | | |
|------------------------------------|--|-------------|
| 1. Public Land Survey | T <u>4S</u> R <u>9W</u> | <u>F-11</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 97 NOV 26 PM 1 32
 Clerk - Register

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert E. Snell, in a field survey on July 31, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
8/21/97

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Surveyors; Set 1/4 Section post..
 Sugar 8" N. 86° E. 25 lks.
 Cherry 24" N. 48° W. 6 1/2 lks.

1872: S. Hodgman, Deputy County Surveyor; "(7) stake, one U.S. witness standing and stump of other correct.

1874: F. Hodgman, County Surveyor; "5(North 1/4 post, Section 33) found stake correct by stump of two witnesses, one down. Set stone with stake driven down beneath it."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1974: D.M. Dreher, RLS #13580; L.C.R.C., L-1, P-385, large stone with "vee" cut on top. "T" rail South 33.0', center line 8" twin walnut N. 75° E., 78.6'. Center line 10" maple, S. 30° W., 34.5'.

1997: Found 18" boulder from 1974 witnesses. A painted drill mark on top fit all witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11: South 1/4 post, Section 28, T. 4 S., R. 9 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on August 21, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 18" boulder with drill mark as set in 1874 survey by F. Hodgman, County Surveyor. Removed boulder and placed a 30" Harrison Monument in its place.

- | | | | |
|------------------------|-------------|-----------|--------|
| P.K. nail in West side | 18" Hickory | S. 40° E. | 33.46' |
| P.K. nail in West side | 28" Walnut | S. 05° W. | 45.38' |
| P.K. nail in East side | 24" Maple | S. 30° W. | 34.18' |
| P.K. nail in East side | 15" Walnut | N. 20° W. | 28.68' |

Signed by Robert E. Snell
 Surveyor's Michigan License No. 9734

Date Nov. 3, 1997