

SURVEY & REMONUMENTATION

FEB 26 1998

1
2

SECTION

LIBER 2 PAGE 237

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Wakeshma Township

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
1997 NOV 26 PM 1 32
Annally Howard
CLERK - REGISTER

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4S</u> R <u>9W</u>	<u>I-02</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on July 30, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
8/21/97 *R.E.S.*

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Surveyors: Set 1/4 section post.
Whitewood 20" N. 53° W. 27 lks.
Beech 12" N. 89° E. 20 lks.

1871: F. Hodgman, County Surveyor; "6 (E 1/4 post, Section 3) found point from stump of 2 witnesses. Set no stake."

1877: F. Hodgman, County Surveyor; "8 (W 1/4 post, Section 2) set stone from stump of one witness."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1972: J. Kester, RLS #16046; L.C.R.C. L-1, P-215, I-02, East 1/4 corner, Section 3. Found stone, raised with 1/2" iron.

42" Ash N.80° W. 35.5'
12" Cherry East 44.35'
50" Oak S.30° E. 79.4'

1997: Found iron over stone with "X". Stone down 20" below surface.

40" Ash - Stump West 35.5', old fence to West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-02: West 1/4 post, Section 2, T. 4 S., R. 9 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on August 21, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found stone with "X" below surface of road. Stone set by F. Hodgman, County Surveyor in a 1877 survey. Placed 12" of 18" Harrison Monument over stone to within 3" of surface.

P.K. nail in West side 64" Oak S. 28° E. 80.04'
P.K. nail in North side 18" Cherry East 44.88'
P.K. nail in North side 18" Maple N. 78° W. 51.14'
P.K. nail in West side 18" Oak S. 54° W. 76.31'

Signed by *Robert E. Snell*
Surveyor's Michigan License No. 9734

Date Nov. 3, 1997