

SURVEY & REMONUMENTATION

NOV 25 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Wakeshma

Kalamazoo
(County)

Located In:	Corner Code #
T4S R9W	I-04
T___ R___	_____
T___ R___	_____
T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on May 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1826: United States Government Surveyors; set 1/4 post.
 Beech 8" S. 78° E. 34 lks.
 Beech 10" S. 79° W. 13½ lks.
- 1884: F. Hodgman, County Surveyor; found marked stone.
 Ash 10" S. 83° W. 83 lks.
 Elm 8" S. 40° W. 86 lks.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1998: Found large stone (18" x 8"-10" Dia.), 8" below surface with very distinct "x" on top.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
5-21-1998

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 I-04: East 1/4 post, Section 10, T. 4 S., R. 9 W., ratified on May 21, 1998 by the Kalamazoo County Remonumentation Program Peer Group and is accepted as the best available evidence of the position of the original corner. Found large stone with distinct "x" on top as found in 1884 survey by F. Hodgman, County Surveyor, placed 6" Harrison monument in concrete over stone and placed monument box over.
- | | | | |
|------------------|----------------------------|-----------|--------|
| Southeast corner | Railroad rail fence corner | N. 88° E. | 29.28' |
| Southeast corner | Railroad rail fence corner | N. 88° W. | 28.59' |
| Center | ½" iron with red cap | S. 45° E. | 21.95' |
| Center | ½" iron with red cap | S. 45° W. | 24.87' |

Signed by Robert E. Snell
 Surveyor's Michigan License No. 9734

Date 10-22-98

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 98 OCT 22 PM 11 38
 Clerk - Register

LIBER 2PAGE 359

Register of Deeds Stamp & File Number

