



LC-000055
 Page: 1 of 1
 10/29/1999 03:52P
 BK-2 Pg-508

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Wakeshma Twp.

SURVEY & REMONUMENTATION
FEB 08 2000
SECTION

Kalamazoo Located in: Corner Code #
 (County)

1. Public Land Survey T 4 S R 9 W I-05
 T R
 T R
 T R
 T R

2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert E. Snell, in a field survey on June 7, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1826: United States Government Surveyors, R. Clark; set post, corner to Sections 10, 11, 14 and 15.
 Beech 14" S. 09° E. 32 lks.
 Beech 16" N. 30° E. 33 lks.
- 1911: E. Strong, County Surveyor; found drilled stone 1' below, Maple 12" N. 50° W. 82 lks., Maple 12" S. 40° E. 1.14 chains.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1999: Found 1" x 12" iron pipe in monument box over large stone. Stone at least 36" x 30" in diameter with drill hole. Stone down 1.25'. Surface marker 0.06' South and 0.01' West of drill hole.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 9-9-1999 *K. S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-05: Southeast corner, Section 10, T. 4 S., R. 9 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on September 9, 1999 and is accepted as the best available evidence of the position of the original corner. Found 1" x 12" pipe in monument box over large stone with drill hole. Stone is believed to be drilled stone found in 1911 by E. Strong, County Surveyor. Placed 10" of 20" Harrison monument over drill hole with monument box over.

PK Nail in North Side	Power Pole	S. 60° E.	95.52'
PK Nail in West Side	32" Maple	S. 20° E.	74.10'
PK Nail in East Side	16" Wild Cherry	S. 30° W.	78.95'
Notch in West Side	Railroad Rail Fence Corner	S. 52° W.	47.42'

Signed by Robert E. Snell
 Surveyor's Michigan License No. 9734

Date 10/25/99