

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Wakeshma Twp.

**SURVEY & REMONUMENTATION**

**FEB 08 2000**

**SECTION**

Register of Deeds Stamp & File Number

<u>Kalamazoo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 4 S R 9 W	J-05
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert E. Snell, in a field survey on June 7, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1826: United States Government Surveyor, R. Clark; set 1/4 Section post.  
 Beech 6" N. 78 1/2° E. 19 lks.  
 Beech 7" N. 62° W. 23 lks.
- 1884: F. Hodgman, County Surveyor; "Rock Bounds" by Nutting, Surveyor and witness stone 50 lks. East.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- 1999: Found no other information on this corner. Found 20" x 12" x 12" ± stone with 5/8" drill hole believed to be "Rock Bounds" by Nutting, Surveyor, noted 3/4" x 24" forming pin down 4 1/2 feet about 4 feet North and about 0.5 feet East of drill hole.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
 9-9-1999

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

J-05: South 1/4 post, Section 11, T. 4 S., R. 9 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on September 9, 1999 and is accepted as the best available evidence of the position of the original corner. Found 20" x 12" x 12" ± stone with 5/8" drill hole as set by Nutting, Surveyor and found in 1884 by F. Hodgman, County Surveyor. Placed 20" Harrison monument over stone with monument box over.

Notch at Top	Railroad Rail Fence Post	S. 08° W.	29.65'
PK Nail in South Side	48" Maple	S. 36° W.	28.80'
PK Nail in South Side	18" Ash	S. 70° W.	63.32'
Center of	Telephone Pedestal	N. 18° W.	52.90'

Signed by Robert E. Snell  
 Surveyor's Michigan License No. 9734

Date 10/25/99