

**SURVEY &  
REMONUMENTATION**

**FEB 26 1998**

LIBER 2 PAGE 239

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Wakeshma Township

Kalamazoo  
(County)

Located in:

Corner Code #

1. Public Land Survey	T <u>4S</u> R <u>9W</u>	L-01
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
•97 NOV 26 PM 1 32  
*James J. Howard*  
CLERK - REGISTER

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on August 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

This corner not established by original Government Surveyors.

1878: F. Hodgman, County Surveyor; "5' (N 1/2 post, Section 1, T. 4 S., R. 9 W.) bisected (1-2) and set stone."

1883: F. Hodgman, County Surveyor; "... A large stone set by R. Nutting for the North 1/2 post, Section 1, Wakeshma stands in the North edge of crossway. This I found correct in a previous survey of Section 1..."

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1997: Found stone with drill mark on top down 34", 6.65' (10 lks.) East of tile (L-13, South 1/4 post, Section 36, Climax). Stone was under 10" root.

NW end of culvert (centerline)	S. 10° W.	13.55'
Tile/Sleeve	West	6.65'

**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP**  
*8/21/97 R. S.*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-01: North 1/4 post, Section 1, T. 4 S., R 9 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on August 21, 1997 and is accepted as a careful and faithful perpetuation of the position of the corner as established in 1878. Found stone down 34" below surface as set by either R. Nutting, Surveyor, or F. Hodgman, County Surveyor, with drill mark on top. Placed 2 stones over corner stone with a 20" Harrison Monument over stone.

P.K. nail in West side	Wooden Fence Post (Corner)	North	26.59'
P.K. nail in South side	14" Elm	N. 40° E.	2.75'
P.K. nail in East side	6" Walnut	S. 30° W.	44.20'
Corner Lot East Leg of	Sign (Arrow) Post	N. 89° W.	1.25'

Signed by *Robert E. Snell*  
Surveyor's Michigan License No. 9734

Date Nov. 25, 1997