

SURVEY & REMONUMENTATION

FEB 26 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2PAGE 218

For corners in Wakeshma Township

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 4S R 9W	M-01
This corner common to Climax (M-13)	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 97 OCT 22 AM 10 41
 J. J. [Signature]
 CLERK - REGISTER
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert E. Snell, in a field survey on June 6, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

A. Description of original monument and accessories and/or subsequent restoration:

1825: United States Government Surveyors; post at corner
 Beech 9" N. 52° W. 14 lks.
 Beech 10" S. 80° E. 21 lks.

1883: F. Hodgman, County Surveyor; Section 36, "3 - found large boulder with drill hole in it set for corner by R. Nutting" - no tile set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Found a large boulder (2'x2'x2') with a 5/8" drill hole in top, 18" below surface of gravel road.

In centerline of road intersection ±

Telephone Pedestal N. 60° E. 26'±
 Telephone Pedestal S. 54° W. 45.9'±

**RATIFIED
 BY KALAMAZOO COUNTY
 REMONUMENTATION
 PEER GROUP**
 8-21-1997 [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-01: Northeast corner, Section 1, T. 4 S., R. 9 W., ratified by Kalamazoo County Remonumentation Program Peer Group on August 21, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found large boulder as set R. Nutting, Surveyor, previous to 1883 survey by F. Hodgman, County Surveyor. Placed 10" of 18" Harrison Monument over stone (drill hole) inside a monument box without lid.

P.K. nail in West side Triple 10" Ash N. 40° E. 49.00'
 P.K. nail in North side 12" Elm N. 78° E. 29.03'
 P.K. nail in South side 10" Butternut S. 50° E. 22.72'
 P.K. nail in South side 30" Maple S. 32° E. 42.63'

Signed by [Signature]
 Surveyor's Michigan License No. 9734

Date Oct. 22, 1997