

SURVEY & REMONUMENTATION

JUL 23 1997

LIBER 2 PAGE 102

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Brady Township
Kalamazoo
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>4S.</u> R <u>10W.</u>	<u>A-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
1996 SEP 31 PM 2 35
REGISTER-REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

IWM Job No. 28528

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on May 9, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1826 - Robert Clark, Jr., Intersected West Boundary 7 lks. North of (phrase ends). Set post at intersection. Corner to Sections 19 & 30. W. Oak 12" S. 56° E. 59 lks., W. Oak 16" N. 21° E. 75 lks.
1869 - S. Hodgman, D.C.S., "Section corner established from the Northeast quarter of Section 25, Schoolcraft which was set from the stumps of two witnesses. Stone corners are set for both. "A" (NW cor., Sec. 30) is 7 lks. North of the corner of Section 25.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron rod in monument box. Removed iron and box and excavated. Found pointed stone 2' below grade. Stone was 0.2' South and 0.7' West of iron location.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP**

6/20/1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found pointed stone was accepted as a careful and faithful perpetuation of the position of the original corner. Placed Harrison Monument over stone and monument box, Accessories:

- S.W. corner of House N. 60° E. 170.29'
- N.W. corner of Church S. 45° E. 287.12'
- Nail & Tab in 12" B. Walnut S. 70° W. 84.21'
- Nail & Tab in 18" Sassafras N. 65° W. 55.84'



Signed by

Allen H. McMachen

Surveyor's Michigan License No.

16935

12/31/96