

FEB 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in BRADY TWP KALAMAZOO (County)

Located In:

Corner Code #

Table with 3 columns: Survey Type, T/R, and Corner Code #. Includes rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Section.

- 4. Lot No. , Recorded Plat
5. Private Claims
6. IWM Job No. 28528

I, Allen H. McMachen, in a field survey on November, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not placed by original government surveyors.

1869 - F. Hodgman, Surveyor, "Set stone on the range line midway between "A" (N.W. cor.) and "G" (S.W. cor.) 40.40 ch. from each in the swamp beside the road on the West.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No corner marker was found. Placed Harrison Monument and monument box on line and halfway between the NW corner (standard marker) and the S.W. corner (standard marker), measuring 2679.42 feet from said corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

This position not established by original government surveyors. Harrison Monument placed is accepted as the best available evidence of the position of the corner. Accessories:

- Harrison Monument in mon. box (E 1/4 cor., Sec. 36, Schoolcraft Twp.) North 19.47'
Nail & Tab (4' High) in NE side 14" Elm N. 45° W. 75.13'
Nail & Tab (5' High) in North side 12" Maple N. 80° W. 46.81'
Nail & Tab (5' High) in NW side U. pole N. 20° E. 107.49'
Nail & Tab (3' High) in NW side 10" Ash N. 55° E. 67.92'



Signed by Allen H. McMachen

Date 12/18/98

Surveyor's Michigan License No. 16935

LIBER 2 PAGE 428
98 DEC 23 AM 3 53
STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
Jimmie J. Howard
CLERK - REGISTER

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 2-13. Cell (10, A) contains a circle with a dot.

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP

2/19/98 R. L. 8