

FEB 08 1999

LIBER 2PAGE 393

SECTION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in BRADY TWP KALAMAZOO (County)

Located In: Corner Code #

Table with 3 columns: Survey Type, T/R coordinates, and Corner Code #. Includes rows for Public Land Survey, Property Controlling, and Miscellaneous.

CLERK - REGISTER

Handwritten signature of clerk/registered professional.

STATE OF MICHIGAN COUNTY OF KALAMAZOO RECEIVED FOR RECORD '98 DEC 15 PM 3 50

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims
6. IWM Job No. 28528

I, Allen H. McMachen, in a field survey on November 5, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1826 - Robert Clark, Jr., D.S., Intersected West boundary 66 lks. South of post. Set post at intersection corner, Secs. 30 & 31, W. Oak 7" N. 43 1/2° E. 62 lks., Y. Oak 9" S. 25 1/2° E. 135 lks..
1869 - F. Hodgman, C.S., "Set stone in place of old corner of former survey."
1922 - Kalamazoo County Road Commission, Placed iron rod near SE cor., Sec. 25, Schoolcraft Twp. for alignment of 24th Street and "Y" Avenue to West.
1957 - W.D. Ingersoll, R.L.S., Found iron rod placed by K.C.R.C. in 1922 and assumed it to be SE 1/4, Sec. 25, Schoolcraft Twp. and measured South 43.56' (gov't jog) and placed iron rod.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No Section corner marker found. Measured South from SE cor., Sec. 25, Schoolcraft Twp. (Std. marker over partial ring of brick) 43.56' (gov't jog) and dug to depth of 4' finding no additional evidence of corner. Placed Harrison marker in mon. box on line between S.E. cor., Sec. 25 and E 1/4 cor., Sec. 36, Schoolcraft Twp. and holding government jog of 66 lks. (43.56') South of said S.E. cor.. Found iron in box placed in 1957 at 7.5' South and 1' East.

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP 12-18-1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Harrison Monument placed per above desc. is accepted as a careful and faithful reestablishment of the position of original corner. Accessories:

- Nail & Tab in 24" Maple N. 30° W. 111.75'
Nail & Tab in 8" Cedar N. 75° W. 71.42'
Nail & Tab in 20" Oak N. 75° E. 95.72'
Nail & Tab in U. Pole N. 65° E. 58.86'
In centerline "Y" Avenue to East



Signed by Allen H. McMachen Surveyor's Michigan License No. 16935

Date 12/15/98

Grid table with columns A-M and rows 2-13. Cell (11, 11) is circled.