

FEB 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER

PAGE 425

For corners in BRADY TWP
KALAMAZOO (County)

Located In:

Corner Code #

CORNER COMMON WITH
M-13, SCHOOLCRAFT TWP.

1. Public Land Survey	T	4S.	R	10W.	A-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 DEC 23 AM 9 53
CLERK - REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on November 25, 1998
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826 - Robert Clark, Jr., D.S.,
(Survey of Brady Twp.), Intersected range line 480 lks. South of temporary six mile post. Set post at intersection corner to Townships 4 and 5 South, Ranges 10 and 11 West, Wh. Oak 9" S. 52° W. 33 lks..
(Survey of Schoolcraft Township), Post at Township corner, Wh. Oak 9" S. 52° W. 33 lks., Hickory 7" N. 48½° E. 41 lks..
1869 - F. Hodgman, C.S., "Found stone N. 52° E. 33 lks from stump of U.S. bearing tree, set post, Maple 8" S. 44½° W. 46 lks., Elm 20" N. 45° W. 64½ lks..
Date? - Old Kalamazoo County Road Commission Plans, Placed iron 3.2' East of "tile" (Sec. cor.), Wits to iron rod, Elm 26" N. 48° W. 45.7', Maple 18" S. 49° W. 33.4', Elm 18" S. 46° E. 42.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" pipe in mon. box in centerline believed to be iron placed by Road Commission. Measured West 3.2' and had magnetic indication of corner. Dug and found iron rod over Clay Tile ringed with stones. Tile was 1.5' below road surface.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12/17/98 R.L.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found clay tile is accepted as a careful and faithful perpetuation of the position of the original corner. Placed standard sleeve over tile with monument box, Accessories:

- N.W. corner of porch foundation S. 50° E. 94.07'
- S.E. corner of house foundation N. 55° W. 98.53'
- Nail & Tab in 20" Sycamore N. 20° W. 93.52'
- Nail & Tab in 10" Walnut S. 70° W. 56.60'
- 1" pipe in monument box East 3.2'



Signed by Allen H. McMachen Date 12/18/98
Surveyor's Michigan License No. 16935