

SURVEY & REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Brady Township		
1. Public Land Survey	T <u>4</u> S R10 W	<u>B-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, John G. Kester, in a field survey on August 13, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826, Set Post, Accessories: W Oak 16 N16E 4.21, Y Oak 14 S89½E 9.29. Survey by Wilkins & Wheaton Engineering (County Surveyors Office) in 1937 Found Brick and placed Iron, Accessories: In Fence Line to North, T.P. N30E 29.85', 6" Elm S45E 46.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original Corner Post & Accessories not recovered. Found ½" Iron in Monument Box over pile of Brick in layer of peat 36" below road surface, Accessories: In line with fence to North, all other accessories gone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7, S¼ Corner Section 18, T4S-R10W, Ratified by Kalamazoo County Remonumentation Program Peer Group on September 16, 1993. Found ½" Iron over Pile of Brick as called for in 1937 survey by Wilkins & Wheaton and is accepted as a careful and faithful perpetuation of the position of the original corner. Removed Monument Box and lowered ½" Iron. Placed 20" Harrison Monument above ½" Iron & pile of Brick and placed Monument Box over Corner.

- Set P.K. Nail in 10" Maple S50W 64.62'
- Set P.K. Nail in P.P. N60W 52.79'
- Set P.K. Nail in P.P. S22W 54.10'
- Set ½" Rebar North 45.95'

Signed by [Signature]
 Surveyor's Michigan License No. 16046
 Kalamazoo County Road Commission

Date 11-4-93

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 93 NOV 4 PM 3 44
 LIBER 1 PG 1010
 Register of Deeds Stamp & File Number

CLERK - REGISTER
[Signature]

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	●												
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

