

1
2

LAND CORNER RECORDATION CERTIFICATE

LIBER 2 PAGE 320

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Brady Township
Kalamazoo
(County)

Located In:

Corner Code #

- | | | | | | |
|--------------------------------------|---|------------|---|-------------|------------|
| 1. Public Land Survey | T | <u>4S.</u> | R | <u>10W.</u> | <u>B-9</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

6. IWM Job No. 29053 & 28528

I, Allen H. McMachen, in a field survey on May 9, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826 - Robert Clark, Jr., D.S., Set quarter Section post, Wh. Oak 14" N. 63° W. 119 lks., Wh. Oak 14" S. 27° E. 104 lks.

1869 - F. Hodgman, C.S., "Found stake from (1) witness. Drove new stake & marked blocked out Wh. Oak S. 27° W. 96 lks."

1869 - Ed Strong, C.S., "Found iron"

Prior to 1957 - Witnesses of unknown origin. In line of fence to South. In line of fence to West. 18" Apple S.E. 28.4'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 OCT 12 PM 1 28
CLERK - REGISTER

Register of Deeds Stamp & File Number

SURVEY & REMONUMENTATION

NOV 25 1998

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 4" diameter pipe 1.3' North of fence line. No fence found to South. Found apple tree stump S.E. 29'. Removed pipe and found what appeared to be a very old iron wagon axle directly below pipe believed to be the iron Ed Strong called for. Top of axle was ±2' deep. Measured West to standard marker at NW cor. @ 2840.22' and measured South to drilled stone found at C¼ cor. @ 2670.43'.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
3/19/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 4" diameter pipe and wagon axle is accepted as the best available evidence of the position of the original corner. Removed wagon axle and replaced with a 30" Harrison Monument, Accessories:

- Nail & Tab in S.E. side of 16" Cherry N. 20° E. 12.95'
- Nail & Tab in North side of 12" Cherry S. 80° E. 39.04'
- Nail & Tab in N.E. side of 16" Cherry S. 20° E. 13.55'
- Nail & Tab in South side 8" Oak S. 80° W. 27.14'



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 10/5/98