

# SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KALAMAZOO

(County)

Located In:

Corner Code #

Brady Township

1. Public Land Survey

T 4 S R 10 W

B-11

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 COUNTY OF KALAMAZOO  
 RECEIVED FOR RECORD  
 94 SEP 21 AM 10 21  
 CLERK - REGISTER  
*[Signature]*

LIBER 1 PG **1171**

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on June 6, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1826 - U. S. Government Survey-Set  $\frac{1}{4}$  Section Post

Burr Oak 7" South 26° West 107 Lks

Hickory 6" South 86 3/4° East 113 Lks

1869 - F. Hodgeman County Surveyor-Quarter Section Corner. Lost and established in the Section Line, 39.98' from East. Set a stone 15" long for Quarter Post. No witness.

1979 - Wilkins & Wheaton Engineering Company-Found stone, placed Monument Box over.

PK Nail in North Root 22" Maple South 35° West 29.35'

PK Nail in East Root 29" Maple North 70° West 51.40'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 - Found stone in Monument Box and one witness tree from 1979.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
 7/21/94 *R.E.S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11 South  $\frac{1}{4}$  Post, Section 30, T. 4 S., R. 10 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on July 21, 1994. Found 15" long stone as called for in 1869 survey of F. Hodgeman and is accepted as a careful and faithful re-establishment (1869) of the original corner. Lowered stone and palced 20" Harrison Marker over with Monument Box over.

PK Nail in East Side 30" Maple South 42° West 30.80' Trav. CL North 4.75'

PK Nail in South Side 36" Maple North 64° West 73.68'

PK Nail in East Side 40" Maple North 02° West 25.30' Fence to South-West 1.0'

PK Nail in South Side 36" Maple North 70° East 67.84'

Signed by

*Robert E. Snell*

Date

9-20-94

Surveyor's Michigan License No.

