

**SURVEY &  
REMONUMENTATION**

FEB 18 1994

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER

1 PG 1012

CLERK - REGISTER

*James H. [Signature]*

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
93 NOV 4 PM 3 44

Register of Deeds Stamp & File Number

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Brady Township		
1. Public Land Survey	T 4 S R 10 W	C-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John G. Kester, in a field survey on August 13, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7		•											
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826, Set Post, Accessories: W Oak 30 S12W 57, W Oak 18 S65E 49.  
Survey in 1880 by F. Hodgeman Found Section Corner Stake & Stone of former survey and renewed it, Accessories: W.O. 6" N73W 147 1/4 Lks, W.O. 7" S75W 129 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Original Corner Post & Accessories not recovered.  
Found 1/2" Iron in Monument Box over Small Pointed Stone with larger Stone alongside believed to be Stone called for in 1880 survey by F. Hodgeman.

**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
C-7, Section Corner 17, 18, 19 & 20, T4S-R10W, Ratified by Kalamazoo County Remonumentation Program Peer Group on September 16, 1993. Found 1/2" Iron in Monument Box over Small Pointed Stone with larger Stone alongside, believed to be Stone called for in 1880 survey by F. Hodgeman, and is accepted as a careful and faithful perpetuation of the position of the original corner. Removed 1/2" Iron and Monument Box, lowered Small Pointed Stone, placed larger Stone on top, placed 20" Harrison Monument above and placed Monument Box over Corner.

- Set P.K. Nail in P.P. South 50.85'
- Set P.K. Nail in 10" Maple N25W 70.49'
- Set P.K. Nail in 10" Maple N20E 48.82'
- Set P.K. Nail in 12" Poplar S22E 38.20'

Signed by *John G. Kester* Date 11-4-93

Surveyor's Michigan License No. 16046  
Kalamazoo County Road Commission