

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALAMAZOO

(County)

Brady Township

1. Public Land Survey

Located In:

Corner Code #

T 4 S R 10 W

C-11

2. Property Controlling
in Section

S ___ T ___ R ___

3. Miscellaneous
Property in Sec.

S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

CLERK - REGISTER

James J. [Signature]

94 SEP 21 AM 10 21

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

LIBER

1 PG1165

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on June 6, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

A. Description of original monument and accessories and/or subsequent restoration:

1826 - U. S. Government Survey-Set Post, Corner to Sections s 29, 30, 31 and 32

White Oak 12" North 55° West 250 Lks
Yellow Oak 8" South 55½° West 216 Lks

1869 - F. Hodgeman County Surveyor-Set Section Corner from stumps of two witnesses. Set stake and stone a little West of Bridge over the Portage (Creek). No Tress near to witness.

RATIFIED *R.E.S.*
**BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP 7/21/94**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1979 - Lost and obliterated Corner. Found Southwest Corner, Section 30, Monument Box perpetuated by previous surveys. Found South ¼ Post Section 30, an elongated stone 15" in length set by F. Hodgeman on line between Southwest Corner and Southeast Corner in 1869. Reset Southeast Corner in line with Southwest Corner and South ¼ Post by retracing Hodgeman surveys of 1869 and 1877. Set concrete monument in Monument Box, 2635.44' East of South ¼ Post, as set by Hodgeman-Wilkins and Wheaton Engineering LCRC L1 P.796--South ¼ Post (stone) West 2,635.44'.

Northwest Guard Rail Post Secured to Bridge Deck Northeast 70.35'
Southwest Guard Rail Post Secured to Bridge Deck Southeast 72.37'

1994 - Found concrete monument in Monument Box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11 Corner for Sections 29, 30, 31 and 32, T. 4 S., R. 10 W., ratified by the Kalamazoo County Remonumentation Peer Group on July 21, 1994. Found 3' x 4" Concrete Plat Monument in Monument Box as called for in survey by Wilkins and Wheaton Engineering Company in 1979 and is accepted as a careful and faithful re-establishment of the position of the original corner. Lowered monument and placed a 20" Harrison Monument over with a Monument Box over.

PK Nail in Top of West End Guard Rail	North 68° East 37.04'	Trav. CL. Rd South 3.3'
PK Nail in Top of West End Guard Rail	South 45° East 41.47'	West Bridge
PK Nail in West Side 8" Walnut	South 54° West 76.45'	Abuttment-East 67.65'
PK Nail in West Side 13" W. Cherry	South 69° West 100.20'	

Signed by

Robert E. Snell
9734
MICHIGAN BOARD OF LAND SURVEYORS

Date

9-20-94

Surveyor's Michigan License No.