

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER

1 PG 1013

For corners in

<u>Kalamazoo</u> <small>(County)</small>	Located In:	Corner Code #
Brady Township		
1. Public Land Survey	T <u>4</u> S R10 W	D-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

CLERK - REGISTER
Jessie B. [Signature]

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 '93 NOV 4 PM 3 44

Register of Deeds Stamp & File Number

I, John G. Kester, in a field survey on August 13, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7		●										
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826, Set Post, Accessories: W Oak 14 N86E 1.87, Tamarack 6 S9E 70. Survey in 1880 by F. Hodgeman, Lost, Bisected the line (3-4) and set Stake, Stone & Brick in the crossway. Accessories: Tam 8 S49E 75 $\frac{1}{4}$, Tam 9 N18W 98 $\frac{1}{2}$, Tam 4 N10 $\frac{1}{2}$ E 95, Tam 6 S33 $\frac{1}{2}$ W 122.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Original Corner Post & Accessories not recovered. Found $\frac{1}{2}$ " Iron in Monument Box over Large Blue Stone above Wood Stake & Brick as called for in 1880 survey by F. Hodgeman, Accessories: None found.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 D-7, S $\frac{1}{4}$ Corner Section 17, T4S-R10W, Ratified by Kalamazoo County Remonumentation Program Peer Group on September 16, 1993. Found $\frac{1}{2}$ " Iron in Monument Box over Large Blue Stone above Stake & Brick called for in 1880 survey by F. Hodgeman and is accepted as a careful & faithful reestablishment of the position of the original corner. Removed Monument Box & $\frac{1}{2}$ " Iron. Placed 30" Harrison Monument above Large Blue Stone, Stake & Brick and placed Monument Box over Corner.

- Center/Top West End 15" C.M.P. S35W 60.71'
- Center/Top East End 15" C.M.P. S30E 61.15'
- Set $\frac{1}{2}$ " Rebar N30W 44.69'
- Set $\frac{1}{2}$ " Rebar N30E 46.16'
- 24" Oak S76E 121.31'

Signed by *John G. Kester* Date 11-4-93

Surveyor's Michigan License No. 16046
 Kalamazoo County Road Commission

