

SURVEY & REMONUMENTATION

2- MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2PAGE 111

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Brady Twp.	T 4S R 10W	D9
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
96 DEC 31 PM 3 22
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Gary D. Hahn, in a field survey on May 3, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1826 South quarter corner established by U.S. Deputy Surveyor Robert Clark, Jr.
Accessories: 14" W. Oak South 86 degrees East 66 links
14" W. Oak North 16 degrees West 30 links

1919 KCRC road plans for 27th St. give distance to Cen. Sec. 20 of 2653.4' and distance to Cen. Sec. 29 of 2655.9'
Witness ties: R.R. iron fence cor. W. 25.8'
R.R. iron fence cor. E. 25.8'
Oak 3" North 85 degrees West 25.8'
Walnut 6" South 35 degrees East 54.0'

1968 I.W.M. found KCRC 1919 iron - set mon. box over iron.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered.

Found 3/4" dia. 2.5' long iron rod in mon. box. Dug a 3' X 6' X 5' deep hole through gravelly sand. Found no additional monument evidence. Road does not appear to have been extensively filled.



RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-19-1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D9, South quarter corner Section 20, Town 4 South, Range 10 West, ratified by Kalamazoo County Remonumentation Peer Group on September 19, 1996. Found 3/4" dia. rod believed to be same as referenced in KCRC 1919 road plans. This rod position is accepted as a careful and faithful perpetuation of the position of the KCRC 1919 corner. Removed rod and set a 20" Harrison Monument in mon. box.
Fnd. nail in 14" Maple South 26 degrees East 53.27' Harrison mon. (cen. sec. 20) North 2653.59'
Fnd. nail in 16" Triple Maple North 85 degrees West 25.78'
Set P.K. nail in twin stump South 87 degrees East 26.40' Harrison mon. (cen. sec. 29) South 2654.12'
Set 1/2" rebar North 45 degrees West 46.36'
R.R. iron fence post East 27.0 +/-
R.R. iron fence post West 26.1 +/-

Signed by Gary D. Hahn
Surveyor's Michigan License No. 38116

Date 12/27/96