

**SURVEY &
REMONUMENTATION**

APR 27 1995

LIBER

1 PG 1195

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo
(County)

Located In:

Corner Code ##

Brady Township

1. Public Land Survey

T 4 S R 10 W

D-12

T _____ R _____

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

CLERK - REGISTER
Janice [Signature]

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
94 DEC 9 AM 9 24

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on June 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1919: Kalamazoo County Road Commission; Field notes and plans show stone for Center of Section 32.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found PK Nail below surface of pavement. Further digging produced a railroad spike and a stone (18" x 18" x 12") with a drill mark, 8" below the surface.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-15-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-12 Center of Section 32, T. 4 S., R. 10 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on September 15, 1994. Found drilled stone as called for in Kalamazoo County Road Commission field note and plans from survey in 1919. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner. Removed PK Nail and Railroad spike, lowered stone and placed a 20" Harrison Monument over stone and a monument box over.

PK Nail in Southeast Side 34" Oak N 50° E 57.50'

PK Nail in Northeast Side 30" Maple S 58° E 51.22'

PK Nail in Northwest Side 45" Walnut S 64° W 52.20'

Notch in Top 6" Steel Post Filled with Concrete N 28° W 45.52' CL of "Y" Ave S 2.6'

Notch in Top 6" Steel Post Filled with Concrete N 54° W 44.72'

Signed by *Robert E. Snell* Date 12-9-94

Surveyor's Michigan License No. 9734