SURVEY & REMONUMENTATION -

APR 2 7 1995

7	
2	

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in	
Kalamazoo	Located In:

Corner Code ##

(County) Brady Township T 4 S R 10 W E-1 1. Public Land Survey _____ R _ __ R _ T _____ R _

LERK-KEGISTER 1 pc 1236

Register of Deeds Stamp & File Number


LIBER


_ ន Τ_ Property Controlling _ T __ __ R _ in Section ____T ____ PI __ Miscellaneous R Property in Sec.

__ , Recorded Plat _

5. Private Claims _

19 _94 I. Robert E. Snell in a field survey on June 2 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:





Description of original monument and accessories and/or subsequent restoration:

U.S. Government Survey; Enter North Boundary at Post.

911 76° 20 Lks North East Wh. 0ak 9" 86° 12 Lks West Wh. 0ak North

F. Hodgman, County Surveyor; Found old stake packed around with stones. Set Post. 1888:

> 18" 45° 46 Lks South West W. Oak 09° 811 47 Lks Hickory South West

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found PK Nail in Road, 1.0' South of Center Line and 33' North of broken plat monument. Three (3) feet below surface, found 3" round tile about 0.4' South of position of PK nail.

NOTE: This Corner is a corner in common with Southeast Corner Section 32 (E-13) Pavilion Township.

> RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION, < PERE GROUP 7-21-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Northwest Corner of Section 4, T. 4 S., R. 10 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on July 21, 1994. Found 3" tile as placed in 1888 remonumentation survey by F. Hodgman and is accepted as a careful and faithful perpetuation of the position of the original corner. Placed a 20" Harrison monument with a monument box over.

North 18° East 33.07 PK Nail in West Side

Northwest Corner of Top Brick on 15" Sq. W. Drive Piller

DV Nail in Northeast Side

12" Poplar Power Pole North 52° East 72.261 South 50° East 45.34 South 24° West 44.76' PK Nail in East Side Center Line "T" Avenue 20" Poplar 1.00' North

Signed by

Date 12/28/94