

FEB 18 1994

COMMISSION

LIBER

1 PG 1026

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'93 NOV 18 PM 3 45

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Brady Township		
1. Public Land Survey	T <u>4</u> S R <u>10</u> W	<u>E-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

James P. Young
CLERK-REGISTER

Register of Deeds Stamp & File Number

I, John G. Kester, in a field survey on August 13, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826, Accessories: W Oak 16 S51 $\frac{1}{2}$ E 88, W Oak 30 N52W 101. Survey by Ed Strong, County Surveyor, 1875, Found hole from one U S Stump. Set Stone with X, Accessories: Y Oak 18 S63W 45.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original Corner and Accessories not recovered. Found $\frac{1}{2}$ " Iron in Monument Box over Stone with chiseled X as called for in 1875 Survey by Ed Strong, Accessories: none found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7, Section Corner 16, 17, 20 & 21, T4S-R10W, Ratified by Kalamazoo County Remonumentation Program Peer Group on September 16, 1993. Found $\frac{1}{2}$ " Iron in Monument Box over Stone with X called for in 1875 Survey by Ed Strong and is accepted as a careful and faithful perpetuation of the position of the original Corner. Removed Monument Box and $\frac{1}{2}$ " Iron. Placed 20" Harrison Monument (with bottom section removed) above Stone with X and placed Monument Box over Corner.

- Set P.K. Nail in P.P. South 34.60'
- Set P.K. Nail in 13" Maple N45W 47.76'
- Set P.K. Nail in 22" Maple N20W 82.69'
- Corner Foundation 2 Story House N45E 129.90'

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-16-93

Signed by *John G. Kester* Date 11-15-93

Surveyor's Michigan License No. 16046

Kalamazoo County Road Commission