

**SURVEY & REMONUMENTATION**

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

7-  
2-

AUG 2 2 1995

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

95 AUG 1 PM 4 08

COMMISSION

For corners in

Kalamazoo

(County)

Brady Township

Located In:

Corner Code #

- |                                    |                            |             |
|------------------------------------|----------------------------|-------------|
| 1. Public Land Survey              | T <u>4</u> S R <u>10</u> W | <u>E-13</u> |
|                                    | T _____ R _____            | _____       |
|                                    | T _____ R _____            | _____       |
|                                    | T _____ R _____            | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____    | _____       |
|                                    | S _____ T _____ R _____    | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____    | _____       |
|                                    | S _____ T _____ R _____    | _____       |

*Jennifer Jans*

CLERK-REGISTER

LIBER

**1 1311**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on July 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1825: United States Government Survey; Corner to Sections 32 and 33 on a Wh. Oak 16"

1875: F. Hodgman, County Surveyor (Kalamazoo County); Found stake and stone of former survey in place of corner tree

1889: A.H. Todd, County Surveyor (St. Joe County); "from Northeast of Section 4 (T. 5 S., R. 10 W.), I ran West 40.36 1/4 Chains. Set a stone notch on top for 1/4 Section Corner on North boundary of Section 4, 80.72 chains to the Corner to Section 4 & 5".

1889: A.H. Todd; "The Northeast Corner to Section 5 (T. 5 S., R. 10 W.) Set many years ago by

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Mr. Nutting in remains of Oak Tree" (orig. Corner)

1975: Wane Mostrom, RLS #14100; LCRC St. Joe County, May, 1975.

E-1 Mendon Township, Grooved Stone Found

24" Oak North 87° East 32.37' 16" Maple West 26.79'

16" Oak South 19° East 68.2' 24" Maple South 28° West 56.46'

1994: Found grooved stone 8" below surface of Road. Stone had been tipped due to road construction. Set stone upright.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**

Note: E-13 Brady is common with E-1 Mendon Twp.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 Corner to Sections 32 and 33 (T. 4 S., R. 10 W.) Ratified by the Kalamazoo County Remonumentation Program Peer Group on May 18, 1995 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found grooved stone in remains of Oak Roots as called for by F. Hodgman in 1875 and A.H. Todd in 1889 surveys. Lowered stone and placed 20" Harrison monument and monument box over stone.

- |                                      |           |                |        |
|--------------------------------------|-----------|----------------|--------|
| PK Nail in South Side                | 45" Oak   | South 88° East | 34.30' |
| PK Nail in Southeast Side            | 48" Maple | South 35° West | 57.61' |
| PK Nail in South Side                | 31" Maple | South 89° West | 27.37' |
| PK Nail in South Side                | 13" Maple | North 24° East | 56.60' |
| Centerline Hallam Road (28th Street) |           | East           | 2.6'   |

Signed by

*Robert E. Snell*

Date

7-27-95

Surveyor's Michigan License No.

9734