

FEB 18 1994

LIBER

1 PG 1027

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

93 NOV 18 PM 3 45

For corners in

Kalamazoo (County)	Located In:	Corner Code -#
Brady Township		
1. Public Land Survey	T 4 S R 10 W	F-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

James P. Young
CLERK-REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John G. Kester, in a field survey on August 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826, Accessories: W Oak 14 N51E 18, W Oak 11 S48E 39.
 Survey by Ed Strong, County Surveyor, 1875, Found Stone by Nutting, Accessories: W Oak 12 N about 50 E 66, W Oak 10 N54 1/2 E 49 or 99.
 Survey by H C Fleming, 1915, Iron Stake, Accessories: Rail fence in line South, 14" Maple S W 27.3', 6" Maple N W 36.3'.
 Survey by Ingersol, Watson & McMachen, 1979, Found Iron Rod, Accessories: 15" Walnut N45W 36.81', P.P. N47E 48.04', P.P. S52E 59.80'. Top N E Cor Tel Ped Box #7600 S40W 32.86'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original Corner and Accessories not recovered.
 Stone by Nutting found by Ed Strong, 1875, and Accessories not recovered.
 Found Spike over 1/2" Iron, Accessories: P.P. S58E 59.80', Top N E Cor Tel Ped Box #7600, S14W 32.86'. Extensive digging (10'x10'x5') revealed nothing else.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-16-93**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7, S 1/4 Corner Section 16, T4S-R10W, Ratified by Kalamazoo County Remonumentation Program Peer Group on September 16, 1993. Found Spike over 1/2" Iron called for in 1979 Survey by Ingersol, Watson & McMachen and is accepted as the best available evidence of the position of the original Corner. Removed Spike and 1/2" Iron. Placed 30" Harrison Monument in their place and placed Monument Box over Corner.
 Set P.K. Nail in P.P. S50E 59.64'
 Set P.K. Nail in P.P. N45E 48.08'
 Set P.K. Nail in P.P. N45W 40.98'
 Set P.K. Nail in Fence Post S25W 57.06'

Signed by *John G. Kester* Date 11-17-93

Surveyor's Michigan License No. 16046
 Kalamazoo County Road Commission