

SURVEY & REMONUMENTATION

JUL 23 1997

COMMISSION

LIBER 2 PAGE 150

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Brady Twp.

| Kalamazoo (County) | Located In: | Corner Code # |
|------------------------------------|-------------|---------------|
| 1. Public Land Survey | T4S R 10W | F-10 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
97 JUN 24 PM 1 17
Clerk - Register
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on April 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 10 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:
This corner not set by original Government Surveyors.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
4-17-1997**

1875: Ed Strong, County Surveyor; center 1/4, stone and side stone 50 lks. West of intersection of 1/4 lines.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1969: Wilkins & Wheaton Engr. Co.; found stone with brick, crockery and small stones around.
12" Power Pole N. 58°-03' E. 62.65'
RR Rail Fence Post S. 42°-53' E. 34.08'
Iron Fence Post N. 86°-17' W. 21.85'
Southeast corner of House N. 25°-36' W. 150.40'
1976: Wilkins & Wheaton Engr. Co., Garth Baden RLS #10679; Center 1/4 post used in plat of "Open Meadow", recorded in L-31, P-14 of plats.
1997: Found stone with "x" on top in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
F-10: Center 1/4 post, Section 28, T. 4 S., R. 10 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on April 17, 1997 and is accepted as best available evidence. Found stone with "x" as used by Ed Strong, County Surveyor in a 1875 survey, in a monument box. Removed monument box and placed 5 1/2" of 20" Harrison Monument in concrete with a new monument box over stone.
Nail/Tab in South Side Power Pole (new) N. 22°-30' E. 80.30'
Nail/Tab in Northwest Side Power Pole (old) N. 53° E. 62.73'
"x" in top RR rail fence post S. 47° E. 34.17'
PK Nail in North Side Power Pole N. 75° W. 142.66'

Signed by Robert E. Snell Date 6-18-97
Surveyor's Michigan License No. 9734