

SURVEY & REMONUMENTATION

7 JUL 28 1997
2 COMMISSION

LIBER 2 PAGE 142

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Brady Twp.

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 4S R 10W	F-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
1997 MAY 27 PM 4 16
Jessie J. Howard
CLERK - REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on April 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP 4-17-1997

R. 28

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
1826: United States Government Surveyors; set 1/4 Section post.
Tamarack 7" S. 38° W. 11 lks.
Tamarack 6" S. 46° E. 43 lks.
1875: Ed Strong, County Surveyor; South 1/4 post 2 stones - found a stake.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1969: Wilkins & Wheaton Engr. Co.; found stone down 3' in water brought up with tapered iron. Placed monument box over.
24" B. Oak N. 21°-36' E. 71.00' 14" Pin Oak S. 12°-57' W. 23.45'
20" Pin Oak S. 46°-14' W. 31.3' 22" B. Oak S. 82°-17' W. 128.31'
1979: Wilkins & Wheaton Engr. Co.; found iron in monument box, 1969 witnesses good except 24" B. Oak N. 21°-36' E. 71.00' uprooted.
1997: Found monument box 4" below surface a 20" tapered iron inside over stone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
F-11: South 1/4 post Section 28, T. 4 S., R. 10 W.; ratified by the Kalamazoo County Remonumentation Program Peer Group on April 17, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found stone down about 2½ feet with 20" tapered iron and monument box over. Stone set by Ed Strong, County Surveyor in 1875 survey. Removed iron and replaced it with 20" Harrison Monument over stone.
PK Nail in West Side 10" Elm N. 46°-30' E. 62.32'
Exist. Nail/Tab in North Side. 24" Oak S. 80°-30' E. 81.89'
PK Nail in East Side 24" Oak S. 08°- W. 23.22'
PK Nail in East Side S. 62°- W. 55.70'

Signed by *Robert E. Snell*
Surveyor's Michigan License No. 9734

Date 5-20-97